



***Engineering 'Lunch & Learn' Series***

***Installation of Pipelines by Bottom Pull  
Methods – Project Examples & Lessons  
Learnt***


***By: Ng Eng Bin  
Principal Consultant  
Submarine Pipelines Consulting Engineers***





Future Lunch & Learn Sessions:

2. Pipeline Riser Installation by Stalk-on Method plus Overview of Other Methods
3. Installation of Floating Facility and Mooring Legs
4. Repairs of subsea pipelines – during installation and during operation
5. An overview of Seabed Intervention Methodologies
6. What are PLETs and how are they installed ??



Agenda:

1. Pipeline (Bundle) Pull from Landfall to Landfall
  - ✓ Preparatory works prior to pipeline installation
  - ✓ Pipeline installation by bottom pull
  - ✓ Backfill, hydrotest & Site reinstatement
2. Pipeline Pull from Landfall to Offshore Barge
  - ✓ Site preparation & offshore vessel setup for pull
  - ✓ Pipe pull & remedial works
  - ✓ Pipeline burial
3. What went well & what went wrong
4. Lessons' Learnt for future project



***Project Example 1: Install bundle of 8 pipelines and 2 Fiber optic Cables from Bukom Island to Tanjung Penjuru @ mainland Singapore***



*Installation Concept: Build Pipeline Bundle at Bukom, then Bottom-pull across Shipping Channel to Penjuru, and Protect Bundle with Rock Berm*

PIPE STRINGING AND STORAGE SITE

WINCH YARD





*Preparatory Works prior to  
Bundle Pull*

*Stringing of Line Pipe to form Pipe Strings*



*Completed Pipe Strings Ready for Bundling prior to Bottom Pull*





*Pulling Head for Pipeline Bundle*



*Preparation of Sheet Pile Cofferdam for Bundle Pull  
(Bukom End)*



## *Preparation of Sheet Pile Cofferdam for Bundle Pull (Penjuru End)*



*Final preparation of cofferdam (Penjuru End)*




*Final Preparation of Cofferdam (Bukom End)*



## *'Hold-back' anchor concept for linear winch*

*Without hold-back anchor, linear winch will move towards the sea instead of pipe moving towards the winch*



*Construction & subsequent removal of 'hold-back' anchor for linear winch*



*Linear winch base construction and arrangement for pipe pulling*





*Dredging of Channel along Pipeline Route to obtain  
Required Seabed Design Profile*



*Drilling & Blasting Works along Pipeline Route to Shatter the Rocks to Enable Dredging*




*Due to Excessive Lengths of Rocks Requiring Blasting, a 2nd Blasting Spread was Used*




*Dredger and 'Drilling & Blasting' Vessel Working Side by Side*



# *Pulling Concept*




INITIAL SET-UP



MIDWAY

*Sheave Block which will be connected to Pipe Bundle  
Pulling Head*



Sheave block enables effective pull force on pipe bundle to be double of the linear winch capacity



*Manouvring Sheave Block for Connection to Pipe  
Bundle Pulling Head*



*Laying of twin wire (from sheave block) along pipeline route, then terminating on lay vessel before connecting to 'triplate'*





*Laying single length pull wire from 'monkey plate' to  
pull winch site*





***Bundle Installation Across Sea  
Channel by Bottom Pull Method***

*1st Pipeline Bundle fully rigged up and ready for pull – waiting for dredging to be completed (see foreground)*

A View of Pulau Ular Stringing Yard



*Attachment of buoyancy drums on Pipe Bundle on Launchway in preparation for Pull*



*Buoyancy tanks strapping arrangement on Pipeline Bundle*




*Initial launch of the pipeline bundle*



*Pipeline bundle ready for 1st launch (note: 2 team members associated with Intecsea – 3rd one was not at site ; guess who he is)*



*Pulling Winch in operation*





# *View of Stringing Yard, Showing Bundle Pull in Progress*



Commencement of pull




Near the end of Pull for this bundled string





*Alignment & tie-in of preceding bundle to the new bundle*




*Resumption of pipeline bundle pull after tie-in to preceding section*




*3 more Bundled Strings left before Completion of  
Installation by Bottom Pull*



*End of the bundle pull*



# *Arrival of Pulling Head/Sheave Block at Destination Point*



## *Installation of Risers on Pipeline Bundle*





***Rock dumping, pre-commissioning  
and site re-instatement***



*Transfer of quarry materials to site storage barge, and then to rock dumping vessel*



*Rock dumping by side stone dumping vessel*



*Backfilling trench at shore approach - by rock dumping vessel (>6m depth) & by clam dredger (<6m depth)*



*Flooding, gauging, cleaning & hydrostatic testing of pipeline bundle*



## *Site re-instatement*




*Site re-instatement (Cont'd)*



***Project Example 2: Install single pipeline from Landfall at Dahej to location  
4.8km offshore & across 4.5km inter-tidal zone  
(to discharge treated water from refinery through diffuser at pipe end to sea)***

**PIPE STRINGING FABRICATION SITE**



*Layout of stringing yard at Dahej – notice half cylindrical buoyancy tanks used (to maximise buoyancy during rising tide)*





*Linear pull winch arrangement on the stationary barge*



*Arrangement for transferring load from pull wire to hold-back anchor,  
& for winding up cable during pull*



*Initiation of pipe pull – pulling head transferred to intertidal zone by onshore equipment, then attached to pull cable*



*Typical pull during high tide (left) & view of pipe during receding tide when no pull could be made*





*Dislodging pull cable from liquefiable soil & straightening it to reduce pull force*



*Typical activities in between pulls during low tide – excavating soil on both sides of pipeline and unburying & straightening pull wire*



*Drums strapped to pull wire to prevent pull wire sinking due to soil liquefaction*



*Welding of new pipe string to preceding string during low tide*





*Discovery of 'deflected' pipeline after pipe pull the night before – the result of reduction in buoyancy spacing unilaterally taken by onshore site supervisor*



Buckle occurred mid-point of deflected pipe section



## *Execution of Plan B – Splitting pipelaying to 2 sections*

- As a result of pipe buckle and inability to pull back the pipeline to repair, pipeline was severed off at buckle location.*
- Pipeline was capped at the ‘shore end’ and partial pipeline pulled to destination.*
- A second segment was pulled until the pulling head just crosses the trailing end of preceding section.*
- Both ends lifted off seabed and tied-in (see picture below)*



*Pipeline along intertidal zone and onshore was buried using onshore equipment (backhoes)*



*Offshore pipeline was buried using a jetsled (white tiger)*



## *What went right & what went wrong*

Item	Project Example 1 (Bundle Pull Singapore)	Project Example 2 (Pipe Pull Dahej)
<b>Pull wire installation</b>	<ul style="list-style-type: none"> <li>Contractor took 4 days to lay &amp; straighten pull cable</li> <li>Contractor surveyed wire &amp; straightened cable until fully satisfied</li> <li>Contractor checked seabed and removed obstacle</li> <li>During pipe pull, Contractor did not experience any issue with pull cable</li> </ul>	<ul style="list-style-type: none"> <li>Contractor laid cable in 6 hours using pontoon pushed by fishing boat in extremely strong current (8 knots)</li> <li>Cable was laid zig-zag</li> <li>During initiation of pull, measured pull force to move the cable was 162T vs 5T estimated due to cable self-burial in liquefiable soil &amp; capstan effect of curvy buried cable</li> </ul>
<b>Pipe pull</b>	Each pull went smoothly	<ul style="list-style-type: none"> <li>Linear winch had difficulty pulling the pipe after a few pulls (as pipeline gets longer)</li> <li>Pull cable needed to be constantly uprooted from seabed and straightened</li> <li>Linear winch broke and there was no spare, costing valuable time</li> <li>Eventually, site supervisors reduced buoyancy tank spacing and pipeline buckled due to excessive deflection of affected pipe section</li> </ul>
<b>Dredging</b>	<ul style="list-style-type: none"> <li>Hard soil was experienced that could not be dredged</li> <li>Drilling &amp; blasting spread mobilized</li> <li>2<sup>nd</sup> B&amp;B spread mobilized</li> <li>Dispute over soil data and VO by Contractor to Owner</li> </ul>	Not applicable
<b>Backfilling</b>	<ul style="list-style-type: none"> <li>Mechanically backfilled with rock &amp; gravel</li> <li>No issue</li> </ul>	<ul style="list-style-type: none"> <li>Jetted down using jetsled</li> <li>Strong current caused delay in deployment – but expected</li> </ul>
<b>Others</b>		Crane on pull vessel broke and there was no spare – vessel was down for long time waiting for spares

## *Lessons' Learnt*

For a successful pipe pull project, it is advisable to stick to the following guidelines:

1. Use a linear winch or similar that can provide constant pull. Waterfall winches are not suitable as the pull capacity reduces as the wire is winched onto the drums.
2. Use supplementary buoyancy device to reduce the required pull force, but it should be used with caution.
  - On-bottom stability of the pipeline should be considered when determining the amount of buoyancy device to use, and unstable pipe can result in undesirable pipe movement during and after the pull, and as demonstrated in an earlier example, could lead to pipe damage.



3. Choose a winch that has excess capacity over what is deemed required based on engineering calculations. In general, there should be a comfortable level of safety factor for all equipment used at site.

## *Lessons' Learnt (Cont'd)*

4. Ensure seabed profile along pipeline route is cleared of obstacles and where necessary, graded to facilitate a smooth pull.
5. Ensure that the pull head of the pipeline does not 'dig in' to the soil during the pull by maintaining its level slightly higher than the preceding pipe, such as by putting a buoyancy device on the pullhead.
6. It is imperative that the pull cable is laid straight along the design pipeline route, and efforts taken to remove any slack or curvature in the cable. The efforts spent on this will pay off during the actual operation.
7. Where the pull cable has a tendency to sink into the seabed, for example, due to soil liquefaction, some device should be used to help the cable self-dislodge, for example, the use of supplementary buoyancy evenly spaced along the cable.



## *Lessons' Learnt (Cont'd)*

8. Checks should be made of the pipeline route prior to pipe pull to ensure that there is no debris or obstruction to the pipe pull.
9. Maintain healthy level of spares at site for all equipment, especially for major equipment, such as for pull winch(es) and cranes.
10. Learn from lessons of past projects (including those from other contractors) and implement all applicable lessons from past projects to the new project being planned or executed.



For more details on bottom pull or other methods of rigid pipeline installation, refer to my new book:  
“Subsea Rigid Pipelines – Methods of Installation”

J-lay Method of Installation



Controlled Depth Tow Method of Installation



Surface-tow Method of Installation



  
PARTRIDGE

**SUBSEA RIGID PIPELINES**  
— Methods of Installation

By Eng-Bin Ng



## SUBSEA RIGID PIPELINES

— Methods of Installation  
By Eng-Bin Ng



S-lay Method of Installation



Reel-lay Method of Installation



Stalk-on Method of Riser Installation



***QUESTIONS ?????***



***Production of Rocks for Pipeline  
Protection***

## *Extraction of rocks at Quarry by drilling & blasting*




*Extracted rocks are crushed to get rocks & stones of varying sizes*



*Crushed rocks are graded into various categories & transferred by conveyor belts to different storage sites*



*Armour rocks are graded using special chain separators (How it works is Quarry's trade secret)*



## *Manual verification of 'cushion' rock grading*





## *Manual verification of 'armour' rock grading*



*Load-out and transportation of engineered rocks to construction site*

